BRUHAT BANGALORE MAHANAGARA PALIKE

3BMP/2017-18/OW/WORK_INDENT29280/CALL-

APPROVED SCHEDULE - B

STP/BBMP/E-PMT/09/2018-19, Date: 25.09.2018

provements of roads, drains and culverts at Muneshwara Block and surroundings at Kodigehalli ward lo. 8

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of PUTTARAJU A ( )	
				In Figures	In Words
1	477.81	KSRRB M300-1. Earth work excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5m, excavated surface levelled and sides neately dressed, the disposed earth to be levelled neatly after breaking of clods complete as per specification. MORTH / Chapter 3 (P.No.142, I.No.19.1 of PW, P&IWTD SR 2016-17)	Cum	254.0	Rupees Two Hundred Fifty Four Only
2	79.64	KSRB 4-1.2: Providing and laying in position plain cement concrete of mix 1:3:6 with OPC cement @ 220kgs, with 40mm and down size graded granite metal coarse aggregates @ 0.892 cum and fine aggregates @ 0.465 cum, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1, 4.2. (P.No.12, I.No.4.2 of PW,P&IWTD S.R 2016-17)	Cum	5900.0	Rupees Five Thousand Nine Hundred Only
3	158.53	Providing laying palin / reinforced cement concrete for Box Drain walls of thicknes 10cm to 20 cm including cenmtering shuttering form work etc. complete as per approved drawiong and design MORTH Specification No. 1500,1700,2200 PCC M 20 Grade upto 0.75 m height using concrete mixture (P.No.265, I.No.37.59.2 of PW, P&IWTD SR 2016-17)	Cum	11250.0	Rupees Eleven Thousand Two Hundred Fifty Only
4	7.93	KSRB - 4.9.2: Providing TMT steel reinforcement Fe500 for R.C.C work including straightening, cutting, bending, hooking, palcing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining memebrs wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications. Specification No. KBS 4.6.3. (P.No.17, I.No.4.46.2 of PW, P&IWTD SR 2016-17)	MT	65000.0	Rupees Sixty Five Thousand Only
5	425.7	Providing and fixing RCC Precast cover slab of 100mm thick for drain in cement concrete M20 using graded granite jelly 20mm and down size with steel reinforcement, including form work, lift charges, curing and concrete finished surfaces on both sides etc, complete and as per drawing and the directions of Engineer in-charge. (Data Rate)	Sqm	1970.0	Rupees One Thousand Nine Hundred Seventy Only
6	7.89	KSRB 4-1.6: Providing and laying in position plain cement concrete of mix 1:2:4 with cement @ 240kgs, with 20mm and down size graded granite metal coarse aggregates @ 0.878 cum and fine aggregates @ 0.459 cum, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1, 4.2. (P.No.12, I.No.4.6 of PW,P&IWTD S.R 2016-17)	Cum	6000.0	Rupees Six Thousand Only

Signature of the Contractor

30/01

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92

30/01